

.
.
.
Land at Yatton
Catchment E @ 2.0 l/s/ha
No Surcharge



Date 14/05/2023 19:57
File CATCHMENT_E_V5.MDX

Designed by RJH
Checked by

Innovyze

Network 2018.1

Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type
1.000	36.500	0.152	240.1	0.086	4.00	0.0	0.600	o	300	Pipe/Conduit
2.000	22.000	0.092	239.1	0.040	5.00	0.0	0.600	o	300	Pipe/Conduit
1.001	28.000	0.070	400.0	0.058	0.00	0.0	0.600	o	450	Pipe/Conduit
1.002	25.400	0.063	403.2	0.055	0.00	0.0	0.600	o	450	Pipe/Conduit
3.000	31.800	0.132	240.9	0.066	4.00	0.0	0.600	o	300	Pipe/Conduit
3.001	10.100	0.042	240.5	0.022	0.00	0.0	0.600	o	300	Pipe/Conduit
1.003	36.600	0.091	402.2	0.076	0.00	0.0	0.600	o	450	Pipe/Conduit
1.004	28.500	0.072	395.8	0.059	0.00	0.0	0.600	o	450	Pipe/Conduit
4.000	42.100	0.176	239.2	0.059	4.00	0.0	0.600	o	300	Pipe/Conduit
5.000	29.200	0.113	258.4	0.060	4.00	0.0	0.600	o	300	Pipe/Conduit
4.001	28.200	0.070	402.9	0.056	0.00	0.0	0.600	o	450	Pipe/Conduit
4.002	27.100	0.068	398.5	0.056	0.00	0.0	0.600	o	450	Pipe/Conduit
6.000	28.200	0.117	241.0	0.058	4.00	0.0	0.600	o	300	Pipe/Conduit
6.001	13.800	0.062	222.6	0.029	0.00	0.0	0.600	o	300	Pipe/Conduit
4.003	23.300	0.058	401.7	0.049	0.00	0.0	0.600	o	450	Pipe/Conduit
4.004	37.200	0.093	400.0	0.077	0.00	0.0	0.600	o	450	Pipe/Conduit
4.005	18.600	0.046	404.3	0.039	0.00	0.0	0.600	o	450	Pipe/Conduit
7.000	25.900	0.108	239.8	0.034	5.00	0.0	0.600	o	300	Pipe/Conduit

Network Results Table

PN	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Vel (m/s)	Cap (l/s)
1.000	6.611	0.086	0.0	1.01	71.4
2.000	6.551	0.040	0.0	1.01	71.6
1.001	6.309	0.184	0.0	1.01	160.7
1.002	6.239	0.239	0.0	1.01	160.0
3.000	6.500	0.066	0.0	1.01	71.3
3.001	6.368	0.088	0.0	1.01	71.4
1.003	6.176	0.403	0.0	1.01	160.2
1.004	6.085	0.462	0.0	1.02	161.5
4.000	6.635	0.059	0.0	1.01	71.5
5.000	6.572	0.060	0.0	0.97	68.8
4.001	6.309	0.175	0.0	1.01	160.1
4.002	6.239	0.231	0.0	1.01	161.0
6.000	6.500	0.058	0.0	1.01	71.3
6.001	6.383	0.087	0.0	1.05	74.2
4.003	6.171	0.367	0.0	1.01	160.3
4.004	6.113	0.444	0.0	1.01	160.7
4.005	6.020	0.483	0.0	1.00	159.8
7.000	6.225	0.034	0.0	1.01	71.5

.
.
.
Land at Yatton
Catchment E @ 2.0 l/s/ha
No Surcharge



Date 14/05/2023 19:57
File CATCHMENT E_V5.MDX
Designed by RJH
Checked by

Innovyze Network 2018.1

Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type
7.001	13.900	0.058	239.7	0.029	0.00	0.0	0.600	o	300	Pipe/Conduit
7.002	20.500	0.085	241.2	0.069	0.00	0.0	0.600	o	300	Pipe/Conduit
1.005	12.500	0.031	403.2	0.000	4.00	0.0	0.600	o	450	Pipe/Conduit
1.006	18.500	1.219	15.2	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit

Network Results Table

PN	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Vel (m/s)	Cap (l/s)
7.001	6.117	0.063	0.0	1.01	71.5
7.002	6.059	0.132	0.0	1.01	71.3
1.005	5.500	1.077	0.0	1.01	160.0
1.006	5.469	1.077	0.0	5.24	833.3

.
.
.
Land at Yatton
Catchment E @ 2.0 l/s/ha
No Surcharge



Date 14/05/2023 19:57
File CATCHMENT_E_V5.MDX
Designed by RJH
Checked by

Innovyze Network 2018.1

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	o	300	S1	8.200	6.611	1.289	Open Manhole	1200
2.000	o	300	S2/1	8.200	6.551	1.349	Open Manhole	1200
1.001	o	450	S2	8.000	6.309	1.241	Open Manhole	1200
1.002	o	450	S3	8.200	6.239	1.511	Open Manhole	1200
3.000	o	300	S4/2	8.150	6.500	1.350	Open Manhole	1200
3.001	o	300	S4/1	8.450	6.368	1.782	Open Manhole	1200
1.003	o	450	S4	8.400	6.176	1.774	Open Manhole	1200
1.004	o	450	S5	8.100	6.085	1.565	Open Manhole	1200
4.000	o	300	S5	8.100	6.635	1.165	Open Manhole	1200
5.000	o	300	S6/1	8.100	6.572	1.228	Open Manhole	1200
4.001	o	450	S6	8.000	6.309	1.241	Open Manhole	1200
4.002	o	450	S7	8.200	6.239	1.511	Open Manhole	1200
6.000	o	300	S8/1	8.100	6.500	1.300	Open Manhole	1200
6.001	o	300	S8/2	8.400	6.383	1.717	Open Manhole	1200
4.003	o	450	S8	8.450	6.171	1.829	Open Manhole	1200
4.004	o	450	S9	8.220	6.113	1.657	Open Manhole	1200
4.005	o	450	S10	7.900	6.020	1.430	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	36.500	240.1	S2	8.000	6.459	1.241	Open Manhole	1200
2.000	22.000	239.1	S2	8.000	6.459	1.241	Open Manhole	1200
1.001	28.000	400.0	S3	8.200	6.239	1.511	Open Manhole	1200
1.002	25.400	403.2	S4	8.400	6.176	1.774	Open Manhole	1200
3.000	31.800	240.9	S4/1	8.450	6.368	1.782	Open Manhole	1200
3.001	10.100	240.5	S4	8.400	6.326	1.774	Open Manhole	1200
1.003	36.600	402.2	S5	8.100	6.085	1.565	Open Manhole	1200
1.004	28.500	395.8	S11	8.000	6.013	1.537	Open Manhole	1200
4.000	42.100	239.2	S6	8.000	6.459	1.241	Open Manhole	1200
5.000	29.200	258.4	S6	8.000	6.459	1.241	Open Manhole	1200
4.001	28.200	402.9	S7	8.200	6.239	1.511	Open Manhole	1200
4.002	27.100	398.5	S8	8.450	6.171	1.829	Open Manhole	1200
6.000	28.200	241.0	S8/2	8.400	6.383	1.717	Open Manhole	1200
6.001	13.800	222.6	S8	8.450	6.321	1.829	Open Manhole	1200
4.003	23.300	401.7	S9	8.220	6.113	1.657	Open Manhole	1200
4.004	37.200	400.0	S10	7.900	6.020	1.430	Open Manhole	1200
4.005	18.600	404.3	S11	8.000	5.974	1.576	Open Manhole	1200

.
.
.
Land at Yatton
Catchment E @ 2.0 l/s/ha
No Surcharge



Date 14/05/2023 19:57
File CATCHMENT_E_V5.MDX
Designed by RJH
Checked by

Innovyze Network 2018.1

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
7.000	o	300	S11/1	8.100	6.225	1.575	Open Manhole	1200
7.001	o	300	S11/2	8.100	6.117	1.683	Open Manhole	1200
7.002	o	300	s11/3	8.100	6.059	1.741	Open Manhole	1200
1.005	o	450	S11	8.000	5.500	2.050	Open Manhole	1200
1.006	o	450	S12	8.000	5.469	2.081	Open Manhole	2100

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
7.000	25.900	239.8	S11/2	8.100	6.117	1.683	Open Manhole	1200
7.001	13.900	239.7	s11/3	8.100	6.059	1.741	Open Manhole	1200
7.002	20.500	241.2	S11	8.000	5.974	1.726	Open Manhole	1200
1.005	12.500	403.2	S12	8.000	5.469	2.081	Open Manhole	2100
1.006	18.500	15.2		5.000	4.250	0.300	Open Manhole	0

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.006		5.000	4.250	0.000	0	0

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	0.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model	FEH D1 (1km)	0.362	Summer Storms	Yes
Return Period (years)	100 D2 (1km)	0.381	Winter Storms	No
FEH Rainfall Version	1999 D3 (1km)	0.330	Cv (Summer)	0.750
Site Location	E (1km)	0.295	Cv (Winter)	0.840
C (1km)	-0.028 F (1km)	2.426	Storm Duration (mins)	30

.
.

.

Land at Yatton
 Catchment E @ 2.0 l/s/ha
 No Surcharge



Date 14/05/2023 19:57
 File CATCHMENT E_V5.MDX

Designed by RJH
 Checked by

Innovyze

Network 2018.1

Online Controls for Storm

Hydro-Brake® Optimum Manhole: S12, DS/PN: 1.006, Volume (m³): 10.5

Unit Reference MD-SHE-0054-2000-2500-2000
 Design Head (m) 2.500
 Design Flow (l/s) 2.0
 Flush-Flo™ Calculated
 Objective Minimise upstream storage
 Application Surface
 Sump Available Yes
 Diameter (mm) 54
 Invert Level (m) 5.469
 Minimum Outlet Pipe Diameter (mm) 75
 Suggested Manhole Diameter (mm) 1200

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	2.500	2.0	Kick-Flo®	0.484	1.0
Flush-Flo™	0.239	1.2	Mean Flow over Head Range	-	1.4

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	1.0	0.800	1.2	2.000	1.8	4.000	2.5	7.000	3.2
0.200	1.2	1.000	1.3	2.200	1.9	4.500	2.6	7.500	3.3
0.300	1.2	1.200	1.4	2.400	2.0	5.000	2.8	8.000	3.4
0.400	1.1	1.400	1.5	2.600	2.0	5.500	2.9	8.500	3.5
0.500	1.0	1.600	1.6	3.000	2.2	6.000	3.0	9.000	3.6
0.600	1.1	1.800	1.7	3.500	2.3	6.500	3.1	9.500	3.7

.
.
.

Land at Yatton
Catchment E @ 2.0 l/s/ha
No Surcharge



Date 14/05/2023 19:57
File CATCHMENT E_V5.MDX

Designed by RJH
Checked by

Innovyze

Network 2018.1

Storage Structures for Storm

Tank or Pond Manhole: S11, DS/PN: 1.005

Invert Level (m) 5.500

Table with 10 columns: Depth (m), Area (m²), Depth (m), Area (m²), Depth (m), Area (m²), Depth (m), Area (m²), Depth (m), Area (m²). Rows show depth increments from 0.000 to 1.000 with corresponding area values.

.
.

.

Land at Yatton
Catchment E @ 2.0 l/s/ha
No Surcharge



Date 14/05/2023 19:57
File CATCHMENT_E_V5.MDX

Designed by RJH
Checked by

Innovyze

Network 2018.1

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH D1 (1km) 0.362 F (1km) 2.426
FEH Rainfall Version 1999 D2 (1km) 0.381 Cv (Summer) 0.750
Site Location D3 (1km) 0.330 Cv (Winter) 0.840
C (1km) -0.028 E (1km) 0.295

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960,
1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water	Surcharged
									Level (m)	Depth (m)
1.000	S1	15 Winter	1	+0%	100/15 Summer				6.694	-0.217
2.000	S2/1	15 Winter	1	+0%	100/15 Summer				6.607	-0.244
1.001	S2	15 Winter	1	+0%	100/15 Summer				6.448	-0.311
1.002	S3	15 Winter	1	+0%	100/15 Summer				6.397	-0.292
3.000	S4/2	15 Winter	1	+0%	100/15 Summer				6.572	-0.228
3.001	S4/1	15 Winter	1	+0%	100/15 Summer				6.458	-0.210
1.003	S4	15 Winter	1	+0%	100/15 Summer				6.350	-0.276
1.004	S5	15 Winter	1	+0%	30/2880 Winter				6.267	-0.268
4.000	S5	15 Winter	1	+0%	100/15 Summer				6.703	-0.232
5.000	S6/1	15 Winter	1	+0%	100/15 Summer				6.643	-0.229
4.001	S6	15 Winter	1	+0%	100/15 Summer				6.446	-0.313
4.002	S7	15 Winter	1	+0%	100/15 Summer				6.396	-0.293
6.000	S8/1	15 Winter	1	+0%	100/15 Summer				6.568	-0.232
6.001	S8/2	15 Winter	1	+0%	100/15 Summer				6.467	-0.216
4.003	S8	15 Winter	1	+0%	100/15 Summer				6.351	-0.270
4.004	S9	15 Winter	1	+0%	100/15 Summer				6.295	-0.268
4.005	S10	15 Winter	1	+0%	30/15 Winter				6.214	-0.256
7.000	S11/1	15 Winter	1	+0%	30/2880 Winter				6.275	-0.250
7.001	S11/2	15 Winter	1	+0%	30/960 Winter				6.191	-0.226
7.002	s11/3	15 Winter	1	+0%	30/600 Winter				6.156	-0.203
1.005	S11	4320 Winter	1	+0%	1/480 Winter				6.139	0.189
1.006	S12	4320 Winter	1	+0%	1/360 Winter				6.180	0.261

PN	US/MH Name	Flooded		Pipe		Status	Level Exceeded
		Volume (m³)	Flow / Cap. (l/s)	Overflow (l/s)	Flow (l/s)		
1.000	S1	0.000	0.17		11.3	OK	
2.000	S2/1	0.000	0.08		4.9	OK	

.
.
.
Land at Yatton
Catchment E @ 2.0 l/s/ha
No Surcharge



Date 14/05/2023 19:57
File CATCHMENT E_V5.MDX
Designed by RJH
Checked by

Innovyze Network 2018.1

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Flooded		Pipe		Status	Level Exceeded
		Volume (m ³)	Flow / Overflow Cap. (l/s)	Flow (l/s)			
1.001	S2	0.000	0.16	22.0		OK	
1.002	S3	0.000	0.20	26.4		OK	
3.000	S4/2	0.000	0.13	8.6		OK	
3.001	S4/1	0.000	0.19	10.7		OK	
1.003	S4	0.000	0.30	42.4		OK	
1.004	S5	0.000	0.34	47.3		OK	
4.000	S5	0.000	0.12	7.8		OK	
5.000	S6/1	0.000	0.13	7.9		OK	
4.001	S6	0.000	0.15	21.2		OK	
4.002	S7	0.000	0.19	25.4		OK	
6.000	S8/1	0.000	0.12	7.6		OK	
6.001	S8/2	0.000	0.17	10.5		OK	
4.003	S8	0.000	0.29	38.9		OK	
4.004	S9	0.000	0.31	44.6		OK	
4.005	S10	0.000	0.39	47.2		OK	
7.000	S11/1	0.000	0.06	4.1		OK	
7.001	S11/2	0.000	0.12	7.1		OK	
7.002	s11/3	0.000	0.23	14.2		OK	
1.005	S11	0.000	0.02	1.9		SURCHARGED	
1.006	S12	0.000	0.00	1.2		SURCHARGED	



30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH D1 (1km) 0.362 F (1km) 2.426
 FEH Rainfall Version 1999 D2 (1km) 0.381 Cv (Summer) 0.750
 Site Location D3 (1km) 0.330 Cv (Winter) 0.840
 C (1km) -0.028 E (1km) 0.295

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status OFF
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960,
 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
 Return Period(s) (years) 1, 30, 100
 Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water	Surcharged
									Level (m)	Depth (m)
1.000	S1	15 Winter	30	+0%	100/15 Summer				6.767	-0.144
2.000	S2/1	15 Winter	30	+0%	100/15 Summer				6.680	-0.171
1.001	S2	15 Winter	30	+0%	100/15 Summer				6.664	-0.095
1.002	S3	15 Winter	30	+0%	100/15 Summer				6.611	-0.078
3.000	S4/2	15 Winter	30	+0%	100/15 Summer				6.634	-0.166
3.001	S4/1	15 Winter	30	+0%	100/15 Summer				6.579	-0.089
1.003	S4	15 Winter	30	+0%	100/15 Summer				6.561	-0.065
1.004	S5	4320 Winter	30	+0%	30/2880 Winter				6.560	0.025
4.000	S5	15 Winter	30	+0%	100/15 Summer				6.776	-0.159
5.000	S6/1	15 Winter	30	+0%	100/15 Summer				6.774	-0.098
4.001	S6	15 Winter	30	+0%	100/15 Summer				6.759	0.000
4.002	S7	15 Winter	30	+0%	100/15 Summer				6.689	0.000
6.000	S8/1	15 Winter	30	+0%	100/15 Summer				6.682	-0.118
6.001	S8/2	15 Winter	30	+0%	100/15 Summer				6.664	-0.019
4.003	S8	15 Winter	30	+0%	100/15 Summer				6.621	0.000
4.004	S9	4320 Winter	30	+0%	100/15 Summer				6.561	-0.002
4.005	S10	4320 Winter	30	+0%	30/15 Winter				6.560	0.090
7.000	S11/1	4320 Winter	30	+0%	30/2880 Winter				6.560	0.035
7.001	S11/2	4320 Winter	30	+0%	30/960 Winter				6.560	0.143
7.002	s11/3	4320 Winter	30	+0%	30/600 Winter				6.560	0.201
1.005	S11	4320 Winter	30	+0%	1/480 Winter				6.560	0.610
1.006	S12	5760 Winter	30	+0%	1/360 Winter				6.590	0.671

PN	US/MH Name	Flooded		Pipe		Status	Level Exceeded
		Volume (m³)	Flow / Cap. (l/s)	Overflow (l/s)	Flow (l/s)		
1.000	S1	0.000	0.52	34.3		OK	
2.000	S2/1	0.000	0.24	14.9		OK	

.
 .
 .
 Land at Yatton
 Catchment E @ 2.0 l/s/ha
 No Surcharge



Date 14/05/2023 19:57
 File CATCHMENT E_V5.MDX
 Designed by RJH
 Checked by

Innovyze Network 2018.1

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Flooded		Pipe		Status	Level Exceeded
		Volume (m ³)	Flow / Overflow Cap. (l/s)	Flow (l/s)			
1.001	S2	0.000	0.47	64.6		OK	
1.002	S3	0.000	0.58	78.5		OK	
3.000	S4/2	0.000	0.41	26.5		OK	
3.001	S4/1	0.000	0.58	32.6		OK	
1.003	S4	0.000	0.91	128.3		OK	
1.004	S5	0.000	0.03	3.7		SURCHARGED	
4.000	S5	0.000	0.35	23.4		OK	
5.000	S6/1	0.000	0.39	24.2		OK	
4.001	S6	0.000	0.45	61.8		OK	
4.002	S7	0.000	0.52	71.7		OK	
6.000	S8/1	0.000	0.36	23.5		OK	
6.001	S8/2	0.000	0.53	32.5		OK	
4.003	S8	0.000	0.83	110.1		OK	
4.004	S9	0.000	0.02	3.5		OK	
4.005	S10	0.000	0.03	3.7		SURCHARGED	
7.000	S11/1	0.000	0.00	0.3		SURCHARGED	
7.001	S11/2	0.000	0.01	0.5		SURCHARGED	
7.002	s11/3	0.000	0.02	1.0		SURCHARGED	
1.005	S11	0.000	0.02	2.4		SURCHARGED	
1.006	S12	0.000	0.00	1.4		SURCHARGED	

.	Land at Yatton
.	Catchment E @ 2.0 l/s/ha
.	No Surcharge
Date 14/05/2023 19:57	Designed by RJH
File CATCHMENT_E_V5.MDX	Checked by
Innovyze	Network 2018.1



100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 0.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
 Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH D1 (1km) 0.362 F (1km) 2.426
 FEH Rainfall Version 1999 D2 (1km) 0.381 Cv (Summer) 0.750
 Site Location D3 (1km) 0.330 Cv (Winter) 0.840
 C (1km) -0.028 E (1km) 0.295

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status OFF
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960,
 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
 Return Period(s) (years) 1, 30, 100
 Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	Surcharged Depth (m)
1.000	S1	15 Winter	100	+40%	100/15 Summer				7.563	0.652
2.000	S2/1	15 Winter	100	+40%	100/15 Summer				7.504	0.653
1.001	S2	15 Winter	100	+40%	100/15 Summer				7.421	0.662
1.002	S3	15 Winter	100	+40%	100/15 Summer				7.353	0.664
3.000	S4/2	15 Winter	100	+40%	100/15 Summer				7.408	0.608
3.001	S4/1	15 Winter	100	+40%	100/15 Summer				7.320	0.652
1.003	S4	15 Winter	100	+40%	100/15 Summer				7.246	0.620
1.004	S5	7200 Winter	100	+40%	30/2880 Winter				7.108	0.573
4.000	S5	15 Winter	100	+40%	100/15 Summer				7.642	0.707
5.000	S6/1	15 Winter	100	+40%	100/15 Summer				7.636	0.764
4.001	S6	15 Winter	100	+40%	100/15 Summer				7.557	0.798
4.002	S7	15 Winter	100	+40%	100/15 Summer				7.499	0.810
6.000	S8/1	15 Winter	100	+40%	100/15 Summer				7.566	0.766
6.001	S8/2	15 Winter	100	+40%	100/15 Summer				7.483	0.800
4.003	S8	15 Winter	100	+40%	100/15 Summer				7.401	0.780
4.004	S9	15 Winter	100	+40%	100/15 Summer				7.183	0.620
4.005	S10	7200 Winter	100	+40%	30/15 Winter				7.108	0.638
7.000	S11/1	7200 Winter	100	+40%	30/2880 Winter				7.108	0.583
7.001	S11/2	7200 Winter	100	+40%	30/960 Winter				7.108	0.691
7.002	s11/3	7200 Winter	100	+40%	30/600 Winter				7.108	0.749
1.005	S11	7200 Winter	100	+40%	1/480 Winter				7.108	1.158
1.006	S12	5760 Winter	100	+40%	1/360 Winter				7.141	1.222

PN	US/MH Name	Flooded Volume (m³)	Flow / Cap. (l/s)	Pipe Overflow Flow (l/s)	Pipe Status	Level Exceeded
1.000	S1	0.000	1.00	65.8	SURCHARGED	
2.000	S2/1	0.000	0.47	29.6	SURCHARGED	

.
 .
 .
 Land at Yatton
 Catchment E @ 2.0 l/s/ha
 No Surcharge



Date 14/05/2023 19:57
 File CATCHMENT E_V5.MDX
 Designed by RJH
 Checked by

Innovyze Network 2018.1

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Flooded		Pipe		Status	Level Exceeded
		Volume (m ³)	Flow / Overflow Cap. (l/s)	Flow (l/s)			
1.001	S2	0.000	0.99	135.9		SURCHARGED	
1.002	S3	0.000	1.28	172.2		SURCHARGED	
3.000	S4/2	0.000	0.77	50.2		SURCHARGED	
3.001	S4/1	0.000	1.17	65.4		SURCHARGED	
1.003	S4	0.000	2.00	282.8		SURCHARGED	
1.004	S5	0.000	0.03	4.3		SURCHARGED	
4.000	S5	0.000	0.64	42.8		SURCHARGED	
5.000	S6/1	0.000	0.71	44.1		SURCHARGED	
4.001	S6	0.000	0.92	125.8		SURCHARGED	
4.002	S7	0.000	1.18	161.8		SURCHARGED	
6.000	S8/1	0.000	0.66	42.3		SURCHARGED	
6.001	S8/2	0.000	1.00	61.2		SURCHARGED	
4.003	S8	0.000	1.89	251.2		SURCHARGED	
4.004	S9	0.000	2.10	297.8		SURCHARGED	
4.005	S10	0.000	0.04	4.4		SURCHARGED	
7.000	S11/1	0.000	0.00	0.3		SURCHARGED	
7.001	S11/2	0.000	0.01	0.6		SURCHARGED	
7.002	s11/3	0.000	0.02	1.2		SURCHARGED	
1.005	S11	0.000	0.02	2.1		SURCHARGED	
1.006	S12	0.000	0.00	1.6		SURCHARGED	